Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
111	350m to 400 m	Rmtr	50.00	620.00	Rupees Six Hundred Twenty Only
112	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) with all lead and lift and directions of the Engineer-In-charge of the work	Rmtr	36.00	1400.00	Rupees One Thousand Four Hundred Only
113	Providing 250mm dia PVC Pipe 6kg/cm as per specification and direction of the Engineer in Charge of the work.with all lead and lift and directions of the Engineer-In-charge of the work	Rmtr	6.00	800.00	Rupees Eight Hundred Only
114	Providing and fixing 175mm Borewell Cap.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	170.00	Rupees One Hundred Seventy Only
115	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 10.00 HP 20 stage.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	45000.00	Rupees Forty Five Thousand Only
116	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008. 50 mm dia including Collar Heavy Class.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	200.00	420.00	Rupees Four Hundred Twenty Only
117	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 12 ,2.10.3, 4.0 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2014-2015 (1x3x4.00 Sqmm PVC cable.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	480.00	130.00	Rupees One Hundred Thirty Only
118	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	3150.00	Rupees Three Thousand One Hundred Fifty Only
119	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44,6.6.6, KPWD Electrical SR 20014-15.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	325.00	Rupees Three Hundred Twenty Five Only

Contractor

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
120	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class.P No. 55/ I No.7.4.4, 4 core 16 Sqmm KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	30.00	150.00	Rupees One Hundred Fifty Only
121	Labour charges for laying of 1.1 K.V class UG cable KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	30.00	15.00	Rupees Fifteen Only
122	Digging or trenching of 0.6 m x 0.5 m wide refilling the trench to the required ground level and consolidating etc., complete as per Civil SR KSRB 1-2 P-7 P No. 68/ I. No. 12-d KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work for cutting road surface	Mtr	25.00	95.00	Rupees Ninety Five Only
123	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 62/ I No.7.12.1, KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work 40mm dia pipe	Mtr	4.00	365.00	Rupees Three Hundred Sixty Five Only
124	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 62/ I No. 7.13.2, KPWD Electrical SR 2007-08.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	290.00	Rupees Two Hundred Ninety Only
125	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia, , P-55, I.No.7.1,KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	2850.00	Rupees Two Thousand Eight Hundred Fifty Only
126	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 45/I No 6.7.3 KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work	No	3.00	250.00	Rupees Two Hundred Fifty Only
127	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13-7.1-4 P.No. 90/I No. 13.55 PWD SR 2016-17.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	1700.00	Rupees One Thousand Seven Hundred Only
128	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 93/ I. No. 13.81.3 PWD SR 2016-17.with all lead and lift and directions of the Engineer-In-charge of the work 50mm dia	No	1.00	250.00	Rupees Two Hundred Fifty Only
129	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc coomplete.with all lead and lift and directions of the Engineer-In-charge of the work	No	2.00	95.00	Rupees Ninety Five Only
130	Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift -loading, unloading and labour charges etc complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	150.00	Rupees One Hundred Fifty Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
131	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 30 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	1700.00	Rupees One Thousand Seven Hundred Only
132	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm @ Rs.0.35 P.No. 40, I. No. 6.40.2, KPWD Electrical SR 2014-15.with all lead and lift and directions of the Engineer-In-charge of the work	Sq.cm	14340.00	0.50	Rupees And Paise Fifty Only
133	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpSet 15HP to 30 HP Star Delta Starter SERDED Rate (P.No. 44, I. No. 6.2.3, KPWD Electrical SR 2014-15).with all lead and lift and directions of the Engineer-In-charge of the work	nos	1.00	14350.00	Rupees Fourteen Thousand Three Hundred Fifty Only
134	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR 2016-17.with all lead and lift and directions of the Engineer-In-charge of the work	Rmtr	210.60	350.00	Rupees Three Hundred Fifty Only
135	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2(b) PRE SR2012-13.with all lead and lift and directions of the Engineer-In-charge of the work 75mm Dia 6 KSC	Rmtr	320.00	130.00	Rupees One Hundred Thirty Only
136	65m Dia PRED SR P.No.14/3, 4.2	Rmtr	200.00	100.00	Rupees One Hundred Only
137	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50mm, and lift upto 1.5m, including cost of all labour complete as per specifications, No. 6/ Item No. 2.11/ PWD SR 2016-17.with all lead and lift and directions of the Engineer-In-charge of the work	Cum	23.00	95.00	Rupees Ninety Five Only
138	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipment with all leads complete as per specifications. No. KBS 13.37 PWD SR - 2016-17).with all lead and lift and directions of the Engineer-In-charge of the work	Each	2.00	2300.00	Rupees Two Thousand Three Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
139	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification.with all lead and lift and directions of the Engineer-In-charge of the work	Cum	54.00	325.00	Rupees Three Hundred Twenty Five Only
140	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specification. Extra for additional lift of 1.5m. or part thereof forexcavation In loose / soft or hard soil including cost of materials, labourcomplete as per specifications.specification. No. KBS.with all lead and lift and directions of the Engineer-In-charge of the work	Cum	54.00	340.00	Rupees Three Hundred Forty Only
141	Providing and filling in foundation with granite / trap borken metal 100mm and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specification. with all lead and lift and directions of the Engineer-In-charge of the work	Cum	10.80	2350.00	Rupees Two Thousand Three Hundred Fifty Only
142	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregate @ 0.892cum and fine aggregates @ 0.465cum machine mixed, machinemixed, concrete laid in layers not exceeding 15 cms, thick well compacted in foundation and plinth, cost of all materials, labour HOM of machinery, curing complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Cum	5.40	5600.00	Rupees Five Thousand Six Hundred Only
143	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Cum	30.28	6700.00	Rupees Six Thousand Seven Hundred Only
144	Providing & removing centering shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies likes, thickness upto 200mm including cost of all materials, labour complete as per specifications	Sqm	31.36	450.00	Rupees Four Hundred Fifty Only
145	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thicknes including cost of all materials, labour complete as per specifications and direction of the Engineer in charge.	Sqm	57.12	325.00	Rupees Three Hundred Twenty Five Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
146	Providing TMT Steel Reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.TMT Bars Fe 500.Lift charges for steel of all diameters for additional floors over ground floor per floor height of 3.5 m. or part thereof cost of labour, complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Mt	4.75	61500.00	Rupees Sixty One Thousand Five Hundred Only
147	Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to ceiling including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification.with all lead and lift and directions of the Engineer-In-charge of the work	Sqm	31.36	225.00	Rupees Two Hundred Twenty Five Only
148	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, Providing and removing scaffolding, cost of materials, labour, curing complete as per specification and Extra for providing and mixing waterproofing compound in cement plaster work at one kg per bag or in the proportion recommended by the manufacturers, for cement mortar 1:4, 18mm thick cost of materials complete as per specifications.	Sqm	57.12	320.00	Rupees Three Hundred Twenty Only
149	Providing and fixing square tank covers of size 24x24.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	1400.00	Rupees One Thousand Four Hundred Only
150	Providing 20mm square M.S.Footrest and fixing in manhole with 1:3:6 cement concrete block of 20x20x10cms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete as per specifications, with all lead and lift and directions of the Engineer-In-charge of the work	No	6.00	300.00	Rupees Three Hundred Only
151	Conveying the excavated debries and over burden earth etc to a lead 20 kms distances by using private vehicles this including the cost of loading and inloading charges etc	Cum	108.00	150.00	Rupees One Hundred Fifty Only
152	Rainy filter: Providing, supplying and commissioning of Rain Water harvesting pump filter with 110mm,fitting & including fitting etc.,complete as per specification (Aproved rates)with all lead and lift and directions of the Engineer-In-charge of the work	No	3.00	6150.00	Rupees Six Thousand One Hundred Fifty Only
153	Providing ,supplying & commissionig of 3 H.P/2.2 KW submersible - three phase mono block pump of Atlanta, Suguna , CRI, Kirloskar and other Equivalent Pumps.with all lead and lift and directions of the Engineer-In-charge of the work	No	1.00	25600.00	Rupees Twenty Five Thousand Six Hundred Only
154	Providing and fixing white vitreous china clay, water closet indian type (squatting pan) of size 580mm with foot rests 100mm S or P trap . 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	28.00	3800.00	Rupees Three Thousand Eight Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl.No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
155	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	33.00	5700.00	Rupees Five Thousand Seven Hundred Only
156	Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I /M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Unit	45.00	4300.00	Rupees Four Thousand Three Hundred Only
157	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Unit	15.00	3400.00	Rupees Three Thousand Four Hundred Only
158	Providing and fixing C.P. brass towel rail 740mm length, 20mm dia with C.P brackets, fixed to wooden cleats with C.P. brass screws including cost of materials, labour complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Unit	30.00	900.00	Rupees Nine Hundred Only
159	Providing gun metal pillar cocks 15mm dia of I class confirming to ISI specifications and fixing them in position as per directions including of cost of materials and fixtures and conveyance to spot. with all lead and lift and directions of the Engineer-In-charge of the work	Each	40.00	300.00	Rupees Three Hundred Only
160	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Each	75.00	300.00	Rupees Three Hundred Only
161	Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	100.00	200.00	Rupees Two Hundred Only
162	Providing and fixing polished granite sink of size 60cms x 90cms of 23cm thick, the sink portion shall be 15cm in depth of shapes oval/round/ square over brick masonry in cement mortar-1:6 including cost and conveyance of all materials, labour for all items of work, HOM of equipment with all lead and lift, loading and unloading, transportion charges and all other incidental charges etc., complete as per specification and direction of the Engineer-in-charge of the work.with all lead and lift and directions of the Engineer-In-charge of the work	Each	14.00	8000.00	Rupees Eight Thousand Only
163	Providing and fixing laboratory sink of white glazed fire clay of size 600x450x200mm with M.S / C.I brackets, C.P brass chain with rubber plug, 32 mm C.P. brass waste, tap with union, brass stop cock complete, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per with all lead and lift and directions of the Engineer-In-charge of the work	Unit	25.00	3800.00	Rupees Three Thousand Eight Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
164	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (Internal work exposed on wall) with all lead and lift and directions of the Engineer-In-charge of the work 15mm nominal OD pipes	m	175.00	135.00	Rupees One Hundred Thirty Five Only
165	20mm nominal OD pipes	m	1100.00	160.00	Rupees One Hundred Sixty Only
166	25mm nominal OD pipes	m	510.00	200.00	Rupees Two Hundred Only
167	32mm nominal OD pipes	m	150.00	300.00	Rupees Three Hundred Only
168	40mm nominal OD pipes	m	130.00	400.00	Rupees Four Hundred Only
169	50mm nominal OD pipes	m	900.00	500.00	Rupees Five Hundred Only
170	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete.(external work) with all lead and lift and directions of the Engineer-In-charge of the work	M	450.00	1600.00	Rupees One Thousand Six Hundred Only
171	Providing and fixing unplasticised PVC connection pipe with brass union 15mm nominal bore length of PVC connection including cost of all materials ,labours and HOM of equipments with all leads complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Set	75.00	300.00	Rupees Three Hundred Only
172	Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	30.00	500.00	Rupees Five Hundred Only
173	Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 25mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	20.00	750.00	Rupees Seven Hundred Fifty Only
174	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 32mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	15.00	1200.00	Rupees One Thousand Two Hundred Only
175	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 40mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	15.00	1500.00	Rupees One Thousand Five Hundred Only
176	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	15.00	2300.00	Rupees Two Thousand Three Hundred Only
177	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	10.00	3000.00	Rupees Three Thousand Only

Executive Engineer
Project Division, Yelahanka

Sl.No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
179	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 80mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Each	10.00	3500.00	Rupees Three Thousand Five Hundred Only
180	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Nos	4.00	1750.00	Rupees One Thousand Seven Hundred Fifty Only
181	Providng and fixing to wall, ceiling and floor unplasticised PVC pipes 6.00 kg / sq.cm working pressure chemp plast / wavin or eqvivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of materials, labour charges, HOM of equipments and testing complete as per speicifications. with all lead and lift and directions of the Engineer-In-charge of the work 40mm dia	Mtrs.	350.00	300.00	Rupees Three Hundred Only
182	50mm dia	Mtrs.	300.00	400.00	Rupees Four Hundred Only
183	63mm dia	Mtrs.	375.00	400.00	Rupees Four Hundred Only
184	75mm dia	Mtrs.	450.00	450.00	Rupees Four Hundred Fifty Only
185	110mm dia	Mtrs.	400.00	550.00	Rupees Five Hundred Fifty Only
186	Providng and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kg / sq.cm working pressure chemp plast / wavin or eqvivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of materials, labour charges, HOM of equipments and testing complete as per speicifications.with all lead and lift and directions of the Engineer-In-charge of the work with 90mm outer dia	M	30.00	535.00	Rupees Five Hundred Thirty Five Only
187	with 110mm outer dia	M	65.00	800.00	Rupees Eight Hundred Only
188	with 140mm outer dia	M	140.00	1400.00	Rupees One Thousand Four Hundred Only
189	with 160mm outer dia	M	90.00	1700.00	Rupees One Thousand Seven Hundred Only
190	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).with all lead and lift and directions of the Engineer-In-charge of the work 10cms x 7.5cms	Each	110.00	300.00	Rupees Three Hundred Only
191	-do- 12.5cms x 7.5cms	Each	5.00	325.00	Rupees Three Hundred Twenty Five Only
192	Providing and fixing 7.5 cms to 15.00 cms dia NP grating 100 mm dia.with all lead and lift and directions of the Engineer-In-charge of the work	Each	115.00	200.00	Rupees Two Hundred Only
193	Providing stoneware gully trap of approved quality and make fixing in M-15 and plastering with CM 1:3 wherever necessary.(Rate includes cost of all materials, fixtures and lead).with all lead and lift and directions of the Engineer-In-charge of the work	Each	5.00	300.00	Rupees Three Hundred Only

Executive Engineer,
Project Division, Yelahanka

Description	Unit	App Qty	Approved Rates of	
			Rate in figures	Rate in words
Constructing brick masonry inspection chamber 455x610mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of ement on walls and bed concrete complete as per tandard design including cost of materials, labour charges, curing complete as per specifications.450x450mm and 450mm depth (inside dimesion) for single pipeline, using table oulded non-modular bricks of class designation 50m in cement mortar 1:5, C.I. coyer withframe (light duty) 50x450mm.with all lead and lift and directions of the Engineer-In-charge of the work	Nos	9.00	6000.00	Rupees Six Thousand Only
Constructing brick masonry inspection chamber 455x610mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover withframe (light duty) 455x610mm internal dimensions, total weight of cover with frame to be not less than 38 kg (weight of cover 23kg and weight of frame 15 kg) R.C.C. top slab with cement concrete M 15 with 20mm and downsize granite metal, foundation concrete M 5 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of ement on walls and bed concrete complete as per tandard design including cost of materials, labour charges, curing complete as per specifications 600x600mm and 450mm depth (clear inside dimesion) for single pipeline, using table moulded non-modular bricks of class designation 50m in cement mortar 1:5, C.I. cover withframe (light duty) 600x600mm.with all lead and lift and directions of the Engineer-In-charge of the work	Nos	12.00	7000.00	Rupees Seven Thousand Only
Constructing brick masonry circular type manhole 0.91 m internal dia at bottom 0.91 m deep and 0.56m dial at top with table moulded non-modular bricks of 50 class designation 50 in cement mortar 1:4, inside cement plastered 12mm thick with cement mortar 1:3, finished with a floating coat of neat cement, foundation concrete M 10 using 40mm and downsize granite metal and making necessary channel in cement concrete M 50 with 20mm and downsize granite metal finished with a floating coat of neat cement, with S.F.R.C. cover and frame (heavy duty, HD-20 grade designation) 560 mm internal diameter confirming IS: 12592, total weight cover and frame to be not less than 182 kg, fixed in cement concrete 1:2:4,20mm and downsize broken granite metal, providing and removing centering, shuttering including cost of materials, labour charges, HOM of machineries complete as per specifications. (Excavation, footrests and 12mm thick cement plaster on the external surface shall be seperately) with all lead and lift and directions of the Engineer-In-charge of the work	Nos	6.00	15000.00	Rupees Fifteen Thousand Only
Providing 20mm square M.S. footrest and fixing in manhole with M 10 cement concrete block of 20x20x1 Ocms, using 20mm and down size metal of size including cost of materials, labour charges, curing complete complete as per specifications. with all lead and lift and directions of the Engineer-In-charge of the work	Nos	8.00	300.00	Rupees Three Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
197	Providng and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kg / sq.cm working pressure chemp plast / wavin or eqvivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of materials, labour charges, HOM of equipments and testing complete as per speicifications.-do- with 110mm outer dia.with all lead and lift and directions of the Engineer-In-charge of the work	M	450.00	800.00	Rupees Eight Hundred Only
198	Drainage Spouts using 100mm class B GI pipe as per drawing and Technical specification including clamps and nuts etc., complete as per specifications.with all lead and lift and directions of the Engineer-In-charge of the work	Nos	30.00	1200.00	Rupees One Thousand Two Hundred Only
199	Supplying, installing, testing and commissioning of submersible pump. of Atlanta, Suguna, CRI, Kirloskar and other Equivalent Pumps of capacity 5 HP/3.7. KW..with all lead and lift and directions of the Engineer-In-charge of the work	Set	3.00	35000.00	Rupees Thirty Five Thousand Only
200	Open Conduit System Supplying heavy gauge PVC conduit pipe .....dia .....mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. with all lead and lift and directions of the Engineer-In-charge of the work 19/20mm dia 2mm thick	Mtr	2350.00	65.00	Rupees Sixty Five Only
201	25mm dia 2mm thick(including fire alarm and cctv)	Mtr	7750.00	80.00	Rupees Eighty Only
202	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of primer of approved make etc. with all lead and lift and directions of the Engineer-In-charge of the work 75x75x65mm	Each	33.00	100.00	Rupees One Hundred Only
203	100x75x65mm	Each	22.00	120.00	Rupees One Hundred Twenty Only
204	135x75x65mm	Each	13.00	120.00	Rupees One Hundred Twenty Only
205	180x90x65mm	Each	264.00	125.00	Rupees One Hundred Twenty Five Only
206	200x90x65mm	Each	12.00	135.00	Rupees One Hundred Thirty Five Only
207	135x160x65mm	Each	98.00	135.00	Rupees One Hundred Thirty Five Only
208	Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. with all lead and lift and directions of the Engineer-In-charge of the work upto 50mm conduit in brick wall	Mtr	2500.00	30.00	Rupees Thirty Only
209	upto 50mm conduit CC floor	Mtr	50.00	45.00	Rupees Forty Five Only
210	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm .... etc. as required.25mm.with all lead and lift and directions of the Engineer-In-charge of the work	Mtr	150.00	35.00	Rupees Thirty Five Only
211	Supplying PVC/GI flexible conduit pipe...mm dia fixing on surface over inverted tapered wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and on either end of the pipe terminated completely.with all lead and lift and directions of the Engineer-In-charge of the work 20mm	Mtr	500.00	30.00	Rupees Thirty Only
212	Supplying And Fixing Metal Fan Box with Round Hook.	No	180.00	110.00	Rupees One Hundred Ten Only

Executive Engineer,
Project Division, Yelahanka

Sl.No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
193	Point wiring using Copper wire with switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A.with all lead and lift and directions of the Engineer-In-charge of the work Short point upto 3Mtr from tapping point to out let via switch	Point	15.00	200.00	Rupees Two Hundred Only
194	Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch	Point	198.00	300.00	Rupees Three Hundred Only
195	Long point above 6Mtr upto 10Mtr from tapping point to out let via switch	Point	218.00	400.00	Rupees Four Hundred Only
196	Two outlet in a row, above 3Mtr upto 6Mtr from tapping point to out let via switches	Point	90.00	500.00	Rupees Five Hundred Only
197	Three outlet in a row, above 6Mts upto 10Mtr from tapping point to out let via switches	Point	75.00	700.00	Rupees Seven Hundred Only
198	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A.with all lead and lift and directions of the Engineer-In-charge of the work 1.5 sqmm	Mtr.	4500.00	22.00	Rupees Twenty Two Only
199	2.5 sqmm(1500MTRS FOR FIRE ALARM)	Mtr.	14500.00	35.00	Rupees Thirty Five Only
200	4 sqmm	Mtr.	7250.00	50.00	Rupees Fifty Only
201	Supplying and drawing Flexible Multicore Cable manufactured with electrolytic grade flexible copper with low conductor confirming to table 3 class 5 of IS:8130-1984 and (Virgin) PVC insulation and sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A.with all lead and lift and directions of the Engineer-In-charge of the work 2C X 2.5Sq.mm	Mtr.	100.00	65.00	Rupees Sixty Five Only
202	4C X 2.5Sq.mm	Mtr.	100.00	125.00	Rupees One Hundred Twenty Five Only
203	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.with all lead and lift and directions of the Engineer-In-charge of the work 1 to 3 Module	Each	33.00	120.00	Rupees One Hundred Twenty Only
204	4 Module	Each	22.00	140.00	Rupees One Hundred Forty Only
205	6 Module	Each	13.00	200.00	Rupees Two Hundred Only
206	8 Module	Each	264.00	225.00	Rupees Two Hundred Twenty Five Only
207	10 Module	Each	12.00	250.00	Rupees Two Hundred Fifty Only
208	12 Module	Each	98.00	300.00	Rupees Three Hundred Only
209	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP A.with all lead and lift and directions of the Engineer-In-charge of the work 6Amps one way.	Each	976.00	75.00	Rupees Seventy Five Only
210	6Amps Two way.	Each	6.00	95.00	Rupees Ninety Five Only
211	6Amps 3way socket.	Each	396.00	150.00	Rupees One Hundred Fifty Only
212	Stepped Fan Regulator.	Each	28.00	300.00	Rupees Three Hundred Only
213	6Amps Bell push	Each	25.00	100.00	Rupees One Hundred Only

Executive Engineer,
Project Division, Yelahanka

Sl.No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
234	6/16Amps universal socket	Each	214.00	160.00	Rupees One Hundred Sixty Only
235	TV/Telephone socket	Each	110.00	100.00	Rupees One Hundred Only
236	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws.with all lead and lift and directions of the Engineer-In-charge of the work	Sq CM	200.00	0.30	Rupees And Paise Thirty Only
237	Supplying 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slab.with all lead and lift and directions of the Engineer-In-charge of the work	No	4000.00	8.00	Rupees Eight Only
238	Supplying and fixing of metal clad industrial plugs and sockets. PLUG 2pole+earth 250V.with all lead and lift and directions of the Engineer-In-charge of the work 10 Amps	Each	10.00	225.00	Rupees Two Hundred Twenty Five Only
239	20 Amps	Each	10.00	250.00	Rupees Two Hundred Fifty Only
240	Supplying and fixing of metal clad industrial plugs and sockets. PLUG 3pole+earth 440V.with all lead and lift and directions of the Engineer-In-charge of the work 20 Amps	Each	10.00	300.00	Rupees Three Hundred Only
241	30 Amps	Each	10.00	325.00	Rupees Three Hundred Twenty Five Only
242	Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp.with all lead and lift and directions of the Engineer-In-charge of the work	Each	10.00	1000.00	Rupees One Thousand Only
243	Supplying surface mounted type mirror optic luminaries for single/Twin 28watts fluorescent lamps cross rising of stove enameled deep coloured M.S.low profile housing complete with all accessories and high purity anodized aluminum reflector assembling along with cross louvers including necessary fluorescent tubes with Energy Saving Electronic Ballast.1x4'-28Watts.with all lead and lift and directions of the Engineer-In-charge of the work	Each	50.00	3000.00	Rupees Three Thousand Only
244	Supplying CFL mirror light fitting with 1x11W CFL lamp, choke, Perspex cover and completely wired for use on 230V 50Hz AC supply.with all lead and lift and directions of the Engineer-In-charge of the work	Each	20.00	700.00	Rupees Seven Hundred Only
245	Supply of recess mounted rolling type LED square or round Down light 12 watts with 4/6W GU 10 LED Lamp Rib Fabricated from Die cast aluminum with white powder coated prewired to mains connector with suitable driver & having swiveling unit of aluminum die cast eye ball & LED Lamp position retained by circular wire spring. 5 years Warranty against any manufacturing defect working under standard electrical condition.with all lead and lift and directions of the Engineer-In-charge of the work	No	375.00	2000.00	Rupees Two Thousand Only
246	Supply of LED Square Recessed Down lighter with 18W System Wattage. Housing shall be with powder coated pressure die cast aluminum alloy with corrosion resistant polyester powder coat & with extended heat sink. Diffuser/cover made of Lexan plastic material. Rated life shall be L70 @ 50000 Hrs. which shall has inbuilt electrical protection like over/under voltage, short circuit, overload, open circuit & miswiring. Driver is on constant current driver output driver @ 0.06A with PF > 0.9 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens. 5 years Warranty against any manufacturing defect working under standard electrical condition.with all lead and lift and directions of the Engineer-In-charge of the work	No	200.00	5100.00	Rupees Five Thousand One Hundred Only
247	Supplying and fixing of round or oblong type bulk head fitting glass cover.with all lead and lift and directions of the Engineer-In-charge of the work	No	10.00	65.00	Rupees Sixty Five Only

Executive Engineer,
Project Division, Yelahanka

Sl. No	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
346	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.with all lead and lift and directions of the Engineer-In-charge of the work 5-32Amps SP	Each	140.00	450.00	Rupees Four Hundred Fifty Only
349	5-32 Amps DP	Each	10.00	900.00	Rupees Nine Hundred Only
350	40-63Amps TPN	Each	10.00	2000.00	Rupees Two Thousand Only
351	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door.with all lead and lift and directions of the Engineer-In-charge of the work 8Way SP &N	Each	9.00	1350.00	Rupees One Thousand Three Hundred Fifty Only
352	12Way SP &N	Each	3.00	1750.00	Rupees One Thousand Seven Hundred Fifty Only
353	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.III - Double Door.with all lead and lift and directions of the Engineer-In-charge of the work 4Way TP &N	Each	14.00	2500.00	Rupees Two Thousand Five Hundred Only
354	8Way TP &N	Each	4.00	3700.00	Rupees Three Thousand Seven Hundred Only
355	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker [ELMCB] 240/450V up to 300mA sensitivity on existing wood/panel board.with all lead and lift and directions of the Engineer-In-charge of the work 32-40 Amps 2 pole	Each	11.00	2800.00	Rupees Two Thousand Eight Hundred Only
356	32-40 Amps 4 pole	Each	6.00	3000.00	Rupees Three Thousand Only
357	63 Amps 4 pole	Each	12.00	3500.00	Rupees Three Thousand Five Hundred Only
358	Supplying and fixing of Metal Socket set of 2pole and earth plugs and socket for incorporating SP and TP MCB (Without MCB). The entire plug and socket shall be mounted in a thermoplastic / powder coated metal box & wired Completely. TP & N.with all lead and lift and directions of the Engineer-In-charge of the work 20Amps	Each	10.00	1250.00	Rupees One Thousand Two Hundred Fifty Only
359	30Amps	Each	10.00	1750.00	Rupees One Thousand Seven Hundred Fifty Only
360	LT KIOSK INCOMER : 800A TPN MDO ACB WITH ACCESSORIES RYB LED INDICATING LAMPS WITH MCB VOLTMETER WITH VSS AMMETER WITH ASS 800/5A CL-1 10VA CT'S BUSBAR & FABRICATION : 800A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	230000.00	Rupees Two Lakh(s) Thirty Thousand Only

Executive Engineer,
Project Division, Yelahanka

	Description	Unit	App Qty	Approved Rates of	
				Rate in figures	Rate in words
	MAIN PANEL EB INCOMER : 630A 4P EDO ACB WITH ACCESSORIES RYB LED INDICATING LAMPS WITH MCB ON OFF TRIP LED INDICATING LAMPS MDM METER 600/5A CL-1 10VA CT'S DG INCOMER : 250A 4P MOT. MCCB WITH ACCESSORIES RYB LED INDICATING LAMPS WITH MCB ON OFF TRIP LED INDICATING LAMPS MDM METER 250/5A CL-1 10VA CT'S INTERLOCKING : ELECTRICAL INTERLOCKING BETWEEN INCOMERS USING CONTACTORS OUTGOINGS : ON OFF TRIP LED INDICATING LAMPS 200A 4P MCCB WITH ACCESSORIES 125A 4P MCCB WITH ACCESSORIES 100A 4P MCCB WITH ACCESSORIES BUSBAR & FABRICATION : 630A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	630000.00	Rupees Six Lakh(s) Thirty Thousand Only
262	GROUND FLOOR PANEL INCOMER : 200A 4P MCCB WITH ACCESSORIES OUTGOINGS : 63A TPN MCB 40A TPN MCB 40A DP MCB 80A TPN MCB BUSBAR & FABRICATION : 200A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	95000.0	Rupees Ninety Five Thousand Only
263	FIRST FLOOR PANEL INCOMER : 100A 4P MCCB WITH ACCESSORIES OUTGOINGS : 63A TPN MCB 40A TPN MCB 40A DP MCB BUSBAR & FABRICATION : 100A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	60000.00	Rupees Sixty Thousand Only
264	SECOND FLOOR PANEL INCOMER : 100A 4P MCCB WITH ACCESSORIES OUTGOINGS : 63A TPN MCB 40A TPN MCB 40A DP MCB BUSBAR & FABRICATION : 100A CAPACITY AL. BUSBAR WITH HEAT SHRINKABLE SLEEVES PANEL FABRICATION WITH 14/16 SWG CRCA SHEET SIEMENS GREY POWDER COATED PANEL	Set	1.00	60000.00	Rupees Sixty Thousand Only

ontractor

Executive Engineer,
Project Division, Yelahanka